

Requester Email

parkinson.charlene@galionschools.org

Attention To

parkinson.charlene

Requested PO Date

12/16/2020

Requisition No

15552

Vendor No

9813 (MUSCO CORPORATION)

Deliver By Date**Deliver To Vendor No**

890112 (Athletic Department - HS)

Deliver ToAthletic Department - HS
KYLE BAUGHN
472 Portland Way N
Galion, OH 44833**Vendor**MUSCO CORPORATION
100 1ST AVENUE WEST
P.O. BOX 808
OSKALOOSA, IA 52577
Fax:
Email:**Requisition Description****Fund to be used/Notes to Approver**REPLACE STADIUM LIGHT POLES - \$75K CONTRIBUTION
FROM FREESE/CITY OF GALION**Terms**

#	Qty	Unit	Desc	Unit Price	Total	Account	Account Code
1	1.0000	1	REPLACE STADIUM LIGHT POLES	\$100,000.0000	\$100,000.00	NEW EQUIPMENT GROUNDS - STADIUM	003-2730-645-0000-000000-011-00-022

Total**\$100,000.00**



100 1st Ave West • PO Box 808 • Oskaloosa, IA 52577
Phone: (800) 825-6020 • Fax: (888) 397-8736
•E-mail joe.fox@musco.com

**Galion High School Football
Galion, OH
New Football Poles
Attn: Kyle Baughn
Dec 10, 2020**

Quote – Materials + Installation+ Demolition

Musco's Light Structure System™ as described below and delivered to the job site..... **\$96,280.⁰⁰**
Adder

Engineered Drawing and Permits are not included in our base bid, IF needed please add..... **\$2,405.⁰⁰**

Equipment Description

Light Structure Green™ System delivered to your site in Five Easy Pieces™

- (4) Pre-cast concrete bases
- New Factory-aimed pole top fitters
- (4) 70' Galvanized Steel pole
- (8) Pole length wire harness
- (8) Electrical Component Enclosures wired without ballasts

Existing Equipment to be Relocated to New Poles

- (30) Musco Fixtures
- (30) 1500W Z-Lamps
- (30) Ballasts
- (30) Capacitors

Scope of Service

Musco proposes the following service:

- 1) ARRANGE SITE DELIVERY & UNLOAD OF MUSCO LIGHT POLE ASSEMBLY
 - 2) REMOVE FENCE AS REQUIRED TO PERFORM WORK
 - 3) AUGER HAUL & INSTALL MUSCO BASES
 - 4) EXCAVATE FROM EXISTING LIGHT POLE LOCATION & EXTEND CIRCUIT TO NEW PROPOSED LOCATION
 - 5) INSTALL FLUSH IN GROUND BOXES AS REQUIRED,EXTEND CONDUIT & WIRING FOR THE LIGHT POLE FEEDER
 - 6) ASSEMBLE LIGHT POLE & ERECT
 - 7) REMOVAL OF EXISTING (6) TOWERS
- REMOVAL OF EXISTING CONCRETE PAD FOUNDATIONS IS NOT INCLUDED

Standard pre-cast concrete foundation installation burial depths will be provided based on standard soils. A soils report and stamped foundation design is not included in the quotation price. Musco can provide a stamped foundation design at an additional charge, if needed. If soils are not adequate for standard foundation designs, additional structural engineering and installation costs may be incurred. These costs will be at the owner's expense and are not included in the quotation price.

Sales tax is not included as part of this quote.

- **Delivery to the job site from the time of order, submittal approval, and confirmation of order details including voltage and phase, pole locations is approximately 30 days. Changes to pole locations after the product is sent to production could result in additional charges.**

Notes

Estimate is based on:

- Shipment of entire project together to one location
- Structural code and wind speed = 2015 115 MPH wind speeds
- Work to be completed Summer 2020

Payment Terms

As agreed upon by Musco Credit Dept.

Thank you for considering Musco for your sports-lighting needs. Please contact me with any questions.

Joe Fox

Service and Parts Sales

Musco Lighting

Phone: 641-676-2340

Mobile: 314-960-2070

joe.fox@musco.com